

Gas Safety Management Plan (Section B)

HMS Flying Fox RNR ARC ACF SCC 15/04/2025

Produced to meet the requirements of the Gas Safety (Management) Regulations 1996

(Gas Safety Management Plan (Section A) covers the requirements of the Gas Safety (Installation and Use) Regulations 1998

ESTABLISHMENT KEY PERSONALITIES (GAS) CONTACTS

| Role | Name | Tel No. | Email |
|--|---------------------|---------------------------------|---------------------------------|
| Head of Establishment | Lt Josh McCreton RM | 0303 382 2874 / 07917 174698 | joshua.mccreton463@mod.gov.uk |
| Establishment's SHEF | CSgt Jeremy Nazarin | 07909 562708 | jeremy.nazarin142@mod.gov.uk |
| Establishments 4C's Coordinator | CSgt Jeremy Nazarin | 07909 562708 | Jeremy.nazarin142@mod.gov.uk |
| Senior DIO Estate Representative or Equivalent | Mark Cubitt | 07955 280440 | wx-est-hd@rfca.mod.uk |
| Site DIO Estate Representative or Equivalent | Mark Armstrong | 07508 129987 | wx-est-mgr3@rfca.mod.uk |
| MMO Site Manager or equivalent | Paul Wakeford | 07356101565 | Paul.wakeford@vivodefence.com |
| Gas Safety Manager (GSM) | Justin Westcott | 07793222820 | Justin.westcott@vivodefence.com |
| Gas Responsible Person (GRP) | Jason Cuthbert | 07592112763 | Jason.cuthbert@vivodefence.com |

The Content of this Gas Safety Management Plan (GSMP) have been Approved by the Gas Safety Manager:

| Signature: | JP Westcott | Date: 15/04/2025 |
|------------|-------------|------------------|
|------------|-------------|------------------|

Authorisation for Implementation

The content and format of this GSMP has been agreed and authorised for implementation by Defence Infrastructure Organisation Technical Services Principal Gas Engineer (DIO TS PGE) and a unique reference number has been generated to support this.

| Approved - | J | Obbard PGE - | · 26 th Feb 2023 |
|------------|---|--------------|-----------------------------|
|------------|---|--------------|-----------------------------|

The Content of this GSMP have been agreed by the Senior DIO Estate Representative or Equivalent and future works following the findings will be supported:

| Signature: | M Cubitt | Date: 07/05/2025 |
|------------|----------|------------------|
|------------|----------|------------------|

The content of this GSMP have been agreed by the Head of Establishment and future works following the findings will be supported.

| Signature: | Josh McCreton | Date: 5 Sep 25 |
|------------|---------------|----------------|
| | | |

Reviews and Amendments

GSMPs are 'living documents' that should be subject to continual review and updating as required. Although the level of attention required will vary considerably depending on the size and complexity of each site, GSMPs should be reviewed at least once per quarter by the GRP. Although it is likely that changes are not required at each review, the date of review and any changes made should be indicated on the tables below. The review of the GSMP will include a site visit to ensure that the site and the content of the GSMP remain valid. The reviews and amendments made will be deleted during the DIO TS three yearly review when the GSMP is re-authorised by the PGE.

| Date | Page | Amendment |
|------------|---------------------|--|
| Date | No. | Amendment |
| 28/09/2022 | All | Initial Development |
| 27/02/2023 | 15 & | Added Network Analysis Data |
| | 23-25 | |
| 27/02/2023 | 13 & | Added Gas Network & Line Drawing References, Icon and |
| | Annex D | Drawings |
| 27/02/2023 | Annex C | Update R/A Dates |
| 14/03/2023 | ii & 1 | Updated HoE Details |
| 12/04/2023 | 10 | Updated Network Pipe Sizing |
| 09/06/2023 | Review Date | Delayed Review Date by 1 Month so Review Date Falls in Line with the Part A |
| 08/09/2023 | 26 | Added Network Analysis & Validation Details |
| 29/12/2023 | Annex C | Updated R/A's Current Preventative Measures |
| 17/01/2024 | ii & 1, 2 | Annual Site Visit Undertaken |
| | & 3 | Updated HoE & Key Personality Details |
| 25/03/2024 | 21 | Section 12 Gas Leak Details Added |
| 26/06/2024 | 18-27 | Added Comments to Sections 6,7,8,10,13,14,15,16,18,19,20,21 |
| | 7 & 10 | Updated network length/Pipework Details after Change of Section |
| | | from Network to Installation Pipework |
| 27/09/2024 | ii & 1, 4 | Updated Head of Estates Details, Updated MAM Details |
| 18/10/2024 | | GSM re-authorisation (previously authorised 30/11/2022) |
| 31/12/2024 | Annex C | Updated R/A's |
| 18/02/2025 | Various | Updated document to reflect VIVO as new MMO including GSM/RP and helpdesk details |
| 07/05/2025 | Various | Updates to HoE details, use of site/occupants and building names. Drawing PDFs yet to be updated. Guardroom number corrected |
| 13/05/2025 | Sec 4.1 | Updated latest network PPM dates |
| 05/09/2025 | ii & 1, 2, 5, 14 | Change of HoE. Update to Site Overview and guardroom number. |
| | | |
| | | |
| | | |
| | | |

| Date | Reviewed by | Authorised by | Comments |
|------------|--------------|---------------|------------------------------|
| 30/11/2022 | M Fenwick | N King | Initial Review |
| 27/02/2023 | M Fenwick | M Fenwick | Quarterly Review |
| 09/06/2023 | M Fenwick | M Fenwick | Quarterly Review |
| 08/09/2023 | M Fenwick | M Fenwick | Quarterly Review |
| 29/12/2023 | M Fenwick | | Annual Review |
| 25/03/2024 | M Fenwick | M Fenwick | Quarterly Review |
| 26/06/2024 | M Fenwick | M Fenwick | Quarterly Review |
| 27/09/2024 | M Fenwick | M Fenwick | Quarterly Review |
| 18/10/2024 | Neville King | Neville King | GSM re-authorisation |
| 31/12/2024 | M Fenwick | M Fenwick | Quarterly Review |
| 27/01/2025 | M Fenwick | M Fenwick | DNV De-Mobilisation Review / |
| | | | Handover |
| 18/02/2025 | J Cuthbert | J Westcott | Update and quarterly review |
| 15/04/2025 | J Westcott | J Westcott | Initial review/approval – |
| | | | Noting VIVO to deliver PPM |
| | | | within next 3 months and |
| | | | assist with planning |
| | | | emergency exercise. |
| 13/05/2025 | J Cuthbert | J Cuthbert | Quarterly Review |
| 20/08/2025 | J Cuthbert | J Cuthbert | Quarterly Review |
| | | | |
| | | | |
| | | | |
| | | | |

FOREWORD

MOD, as a gas conveyor within Great Britain, has submitted an Exemplar Gas Safety Case (MOD GSC) to demonstrate compliance with the Gas Safety (Management) Regulations 1996 (GSMR). Maintenance Management Organisations (MMO's) are engaged who have the overall contractual responsibility to operate and maintain the gas network assets under their Contract, including the management of the safe flow of gas within the system and the provision of an emergency service. The MOD delegate specific duties to the MMO but accountability for gas safety on each site rests with the Head of Establishment.

The MOD GSC considers all parts of the MOD estates gas supply system that forms part of the gas supply network. This includes all parts of the MOD estates network from the External Gas Distribution Network (EGDN) connection point to the emergency control valve (ECV) of individual consumers. The MOD GSC considers primarily those matters that relate to the management of the safe flow of gas within the system and the provision of an emergency service.

The conclusions of the assessments within the MOD GSC are:

- There is an adequate safety management system in place to manage the flow of gas safely in its gas supply system.
- Adequate arrangements are in place to comply with the requirements of GSMR and allow co-operation with other bodies that have duties under the regulations.
- Adequate arrangements are in place for ensuring that gas conveyed within the system meets the standards for composition and pressure.
- Adequate arrangements are in place for dealing with reports of gas escapes and investigation of incidents.
- Adequate arrangements have been made to ensure that the risk of a supply failure is minimised.
- Adequate arrangements have been made to ensure that supply emergencies are managed safely.

The MOD GSC is a generic document that outlines the gas safety systems and processes in place for gas networks within the MOD estate. Site-specific details and arrangements are contained within this establishment Gas Safety Management Plan (Section B) (GSMP). As a site-specific component of the MOD GSC, this GSMP has the same legal standing under GSMR.

The layout and structure of this GSMP mirrors that of its parent GSC

Following initial approval by the DIO PGE, the GSM is required to reapprove this GSMP annually. GSMP must be submitted to DIO TS every three years for PGE authorisation.

The HoE and Senior DIO Estate Representative or Equivalent would only be required to resign this GSMP annually following the GSM reapproval, unless significant changes to the gas system or a change in one of these key personalities occurs.

GSMP Section A documents detail MOD measures to ensure compliance with the Gas Safety (Installation and Use) Regulations 1998 (GSIUR) for installation pipework (downstream of Emergency Control Valves).

Although the legal status of this document applies in the UK only, the MOD apply the same requirements to the management of natural gas networks on its overseas estate in accordance with the currently published Secretary of State's Health and Safety policy statement.

Contents

| ES | STABLISHMENT KEY PERSONALITIES (GAS) CONTACTS | |
|----|--|----------|
| F | ORWARD | v |
| 1 | THE DUTY HOLDER AND ESTABLISHMENT LEVEL KEY PERSONALITIES | |
| | 1.1. GAS SAFETY CASE DUTY HOLDER | |
| | 1.2. DIO TECHNICAL SERVICES PRINCIPAL GAS ENGINEER (PGE) | |
| | 1.3. ESTABLISHMENT PERSONALITIES | |
| | 1.4. MAINTENANCE MANAGEMENT ORGANISATION (MMO) | |
| | 1.5. ADDITIONAL GAS CONTACTS. | |
| 2 | OPERATION UNDERTAKEN | 5 |
| | 2.1 SITE OVERVIEW | 5 |
| | 2.2 DOCUMENT CENTRE | 5 |
| | 2.3 PURPOSE OF PIPELINE(s) | 5 |
| | 2.4 CONSUMERS | <i>6</i> |
| | 2.5 DESCRIPTION OF MOD GAS NETWORKS. | <i>6</i> |
| | 2.6 PRIMARY METER DETAILS. | |
| | 2.7 UTILISATION METERS (METERS SUPPLIED DIRECTLY FROM THE MOD GAS NETWORK) | |
| | 2.8 SECONDARY PRESSURE REGULATING INSTALLATIONS (PRIS) | |
| | 2.9 EMERGENCY CONTROL VALVES (ECVS) | |
| | 2.10 MOD NETWORK PIPELINE DETAILS. | |
| | 2.11 NETWORK INTERCONNECTION | |
| | 2.12 SENSITIVE AND CRITICAL LOADS. | |
| | 2.13 STANDBY ALTERNATIVE FUEL SUPPLIES. | |
| 3 | PLANT AND PREMISES | 13 |
| | 3.1 DRAWINGS | |
| | 3.2 ADDITIONAL DRAWINGS | |
| | 3.3 RESPONSIBILITY INTERFACES AND ACCESS ARRANGEMENTS | 14 |
| 4. | . OPERATION AND MAINTENANCE DOCUMENTATION | 15 |
| | 4.1 MOD NETWORK MAINTENANCE | |
| | 4.2 IRON PIPEWORK. | |
| 5. | . RISK ASSESSMENTS | 17 |
| | 5.1 MODEL RISK ASSESSMENTS. | |
| | 5.2 ADDITIONAL SITE-SPECIFIC RISK ASSESSMENTS. | |
| 6. | . SAFETY MANAGEMENT SYSTEMS | 18 |
| | . EMPLOYEE COMPETENCE | |
| 8. | . CONTRACTORS | 18 |
| | . HEALTH AND SAFETY COMMUNICATION – INTERNAL | |
| | 9.1 HEALTH AND SAFETY COMMUNICATION | |
| 11 | 0. HEALTH AND SAFETY COMMUNICATION – EXTERNAL | |
| | 1. AUDITS | |
| | 11.1 GSM AUDIT | |
| 1 | 2. CO-OPERATION | |
| 14 | 12.1 EMERGENCY EXERCISES | |
| 1 | 3. EMERGENCY EXERCISES | |
| 1 | J. LIVIENGEIVET JENVILE REJEVIVJE I U UMJ EJLAPEJ | |

VIVO Business

| 14. | INVESTIGATIONS | 21 |
|------------|---|----|
| <i>15.</i> | GAS QUALITY | 22 |
| 16. | CONTINUITY OF SUPPLY | 22 |
| 17. AC | DEQUATE NETWORK PRESSURE | 23 |
| 17.1 | NETWORK ANALYSIS. | 23 |
| | DESIGN MINIMUM PRESSURE. | |
| 17.3 | NETWORK ANALYSIS RESULTS. | 23 |
| | NETWORK VALIDATION SURVEY. | |
| | NETWORK VALIDATION SURVEY RESULTS. | |
| 17.6 | CORRECTIVE MEASURES | 26 |
| 18. | GAS SUPPLY EMERGENCIES | 26 |
| 19. | GAS QUALITY – SOLE CONVEYER | 26 |
| 20. | DISCONTINUING GAS SUPPLY | 26 |
| 21. | RESTORATION OF SUPPLIES | 27 |
| ANNEX | A - ABBREVIATIONS | 28 |
| ANNEX | B - SITE LAYOUT DRAWINGS. | 1 |
| ANNEX | C - MODEL RISK ASSESSMENTS | 5 |
| ANNEY | D - ADDITIONAL SITE-SDECIEIC PISK ASSESSMENT TEMPLATE | 20 |

1 THE DUTY HOLDER AND ESTABLISHMENT LEVEL KEY PERSONALITIES

1.1. Gas Safety Case Duty Holder.

The duty holder for the MOD Gas Safety Case is the Permanent Under Secretary for Defence (PUS). However, day to day responsibility for the preparation and maintenance of the document is delegated to the DIO TS Head of Engineering and Construction, who also has the responsibility for managing the system in accordance with the Safety Case. PUS delegates maintenance responsibility to the Top-Level Budget Holders (TLB's), to manage safety of the gas network. The TLB's utilise MOD Contracts i.e. MMOs who have responsibility for maintaining the gas network on behalf of the MOD.

Name: Permanent Under Secretary

Address: Main Building

Horse Guards Parade

Whitehall London SW1A 2HB

1.2. DIO Technical Services Principal Gas Engineer (PGE).

The PGE assumes the role of Senior Authorising Authority which is a term used within the MOD to recognise the authority of the person responsible for overseeing the appointment of, and auditing Authorising Engineers (AEs). For Gas the AEs are replaced by Gas Safety Managers (GSMs).

Name: Jeremy Obbard

Address: DIO HQ

2:

Whittington Barracks

Lichfield WS14 9TJ 07748 903260

☑: Jeremy.obbard100@mod.gov.uk

| 1.3. Establishment Personalities. | | | |
|--|--|--|--|
| Name of Establishment: Establishment Address: | HMS Flying Fox HMS Flying Fox Winterstoke Road Bristol BS3 2NS | | |
| Head of Establishment (HoE) (This is the most senior MOD person identified, by the chain of command, as responsible for the establishment. The HoE holds accountability for ensuring site compliance with the requirements of GSMR and the MOD GSC, including this GSMP.) | Name: Position: Organisation: Address: | Commanding Officer Royal Marines Reserve Bristol | |

| Establishment 4Cs | Name: Position: Organisation: Address: | CSgt Jeremy Nazarin Unit Logistics Officer Royal Marines Reserve Bristol HMS FLYING FOX Winterstoke Road BRISTOL BS3 2NS 07909 562708 Jeremy.nazarin142@mod.gov.uk |
|---|--|--|
| Establishment SHEF | Name: Position: Organisation: Address: | CSgt Jeremy Nazarin Unit Logistics Officer Royal Marines Reserve Bristol HMS FLYING FOX Winterstoke Road BRISTOL BS3 2NS 07909 562708 Jeremy.nazarin142@mod.gov.uk |
| Senior DIO representative or equivalent (This may be the SEFM, but will vary depending on the contract this establishment falls under) | Name: Position: Organisation: Address: | Mark Cubitt Head of Estates Wessex Reserve Forces' & Cadets' Association Mount House Mount Street Taunton Somerset TA1 3QE 07955 280440 wx-est-hd@rfca.mod.uk |
| Site Guardroom (24 Hours) | 2 : | MGS Guardroom on site manned 24/7 0117 953 0869 / 07773 154105 |
| Site emergency services (Are they 24 Hours?) | Fire 1 : Police 1 : Medical 1 : | 999 999 999 |

| 1.4. Maintenance Management Organisation (MMO). | | | | |
|---|------------------|-----------------------|--|--|
| The MMO for this es | tablishment is: | VIVO Defence Services | | |
| MMO Customer Services | Organisation: | VIVO Helpdesk | | |
| (not 24 hours) | | Helpdesk | | |
| | Address: | 25 Goodlass Road | | |
| | | Hunts Cross | | |
| | | Liverpool | | |
| | | L24 9HJ | | |
| | | | | |
| | ≘ : ⊠: | 0800 030 9320 | | |

| MMO Helpdesk – Gas | Organisation: | VIVO Helpdesk |
|----------------------------|---------------|--------------------------------|
| Emergencies Only | | Helpdesk |
| (24 Hours) | | 25 Goodlass Road |
| , | | Hunts Cross |
| Note: Please do not | | Liverpool |
| contact the general public | | L24 9HJ |
| National Gas Emergency | ☎: | |
| Service for suspected gas | | |
| escapes on RFCA | | 0800 030 9320 |
| infrastructure. | | |
| Site Contact | Name: | CSgt Jeremy Nazarin |
| | Organisation: | Unit Logistics Officer |
| | Address: | Royal Marines Reserve Bristol |
| | | HMS FLYING FOX |
| | | Winterstoke Road |
| | | BRISTOL |
| | | BS3 2NS |
| | ☎: | 07909 562708 |
| | ⊠: | Jeremy.nazarin142@mod.gov.uk |
| Gas Safety Manager | Name: | Justin Westcott |
| (GSM) | Organisation: | Vivo Defence |
| | Address: | Bldg. 003, CTCRM Lympstone |
| | | Nr Exmouth |
| | | Devon |
| | | EX8 5AR |
| | ☎: | |
| | ⊠: | |
| Gas Responsible Person | Name: | |
| (GRP) | Organisation: | |
| | Address: | Imjin Barracks |
| | | Innsworth |
| | | Gloucester |
| | | Gloucestershire |
| | ☎: | |
| | ⊠: | 07592 112763 |
| | | Jason.cuthbert@vivodefence.com |

| 1.5. Additional Gas Conta | acts. | |
|---------------------------|---------------|------------------------------------|
| External Gas Distribution | Organisation: | Wales & West Utilities |
| Network (EGDN) | Address: | Wales & West House, Spooner Close, |
| | | Celtic Close |
| | | Coedkernew |
| | | Newport |
| | | NP10 8FZ |
| | ☎: | 0800 912 2999 |
| | ⊠: | Steve.Harding@WWUtilities.co.uk |
| Meter Asset Manager | Organisation: | National Gas Metering |
| (MAM) | Address: | Pavilion Drive |
| | | Witton |
| | | Birmingham |
| | | B6 7BB |
| | 2 : | |
| | ⊠: | enquirydesk@nationalgrid.com |
| | | |

| Gas Supplier | Organisation: Address: | |
|---|------------------------|---|
| DIO SD EUS (Service, Delivery, Energy, | ≘ : ⊠: | 0121 311 3854 DIOSDEUS-enaccounts@mod.gov.uk |
| Utility and Sustainability) | | <u> </u> |
| National Gas Emergency | 2 : | 0800 111 999 |
| Centre (24 Hours) | | |
| National Emergency | Fire 🖀: | 999 |
| Services (24 Hours) | Police 🖀: | 999 |
| . , | Medical 2 : | 999 |

2 OPERATION UNDERTAKEN

2.1 Site Overview.

A brief description of the establishment and its current use. This should include how many separate sites are present, number of buildings being supplied by gas, what the gas is used for and number of personnel who will be affected by a gas outage. Any critical loads should be initial highlighted here (quick reaction forces, large medical facilities, temp controlled ammunition stores etc)

HMS Flying Fox is a single site establishment with five major buildings on site, three of which are supplied by gas –

- The main building supplied direct from the MoD network.
- 'Tech Block' supplied direct from the MoD network.
- Navy Regional HQ Building supplied via below ground installation pipework.

The main Building is used for storage, Office Space, Kitchen, Drill Hall (including events), classrooms and a bar/lounge.

The Tech Block is used for office space and stores.

The Navy Regional HQ building is used for office space.

The site is currently occupied by Royal Marines Reserves, Royal Navy Reserves, University Royal Navy Unit, Royal Naval Regional Headquarters for Wales and Western England, the Royal Navy Regional Support Unit, HQ Southwest Area Sea Cadets and Bristol ACF Winterstoke Road Detachment.

During working hours there are around 20-30 people on site. In the evenings and at weekends there can be 20-40 people on site for training, including use of overnight accommodation. There can be over 100 people on site for periodic functions, events or parades. The site has a guardroom manned 24/7.

2.2 Document Centre.

Location of the establishment Gas Document Centre containing all information relating to the gas systems at this establishment (Ref: MOD GSC 10.2) and contact details if different to the GRP.

The Gas document centre is held electronically by VIVO on the Sharepoint system.

The aim is for this to eventually be accessible via a QR code for each site.

2.3 Purpose of Pipeline(s).

A brief description of demarcation agreements between the EGDN, MAM and MOD. Number of MOD networks including operating pressures and number of buildings being supplied direct from the EGDN. End users of gas being supplied such as accommodation, workshops, catering facilities etc.

The gas supply to HMS Flying Fox is fed from the Wales and West Utilities (WWU) Medium pressure (MP) network and is a single feed onto site which supplies the site twin stream Bulk Fiscal Primary Meter 01.

The Bulk Fiscal meter feeds the individual MoD Low pressure (LP) network on site at 30.7 mbar which in turn supplies gas to 3 buildings.

The buildings supplied by the MoD network are:

- The Main Building
- The Tech Block

The gas supply to the Naval Regional Headquarters building is fed via installation pipework from the main building.

The gas in these buildings is used for heating, hot water and catering. The MoD network commences after the Bulk Fiscal Meter outlet valve.

The MoD is responsible from the meter outlet valve of the Bulk Fiscal Primary Meter up to and including the appliances in the buildings.

2.4 Consumers.

Consumers can be broadly categorised as domestic or industrial / commercial. Gas supplies to domestic consumers are normally prioritised above industrial / commercial consumers.

| Domestic consumers supplied from the MOD network: | 0 |
|---|---|
| Industrial / commercial consumers supplied | 2 |
| from the MOD network: | |

2.5 Description of MOD Gas Networks.

A description of the MOD gas network(s) including location of primary meter(s), twin stream or single stream, primary meter kiosk construction and condition. Pipeline length, material, diameter, pressure, age and condition. Are any PRIs present and number of buildings being supplied?

There is a single EGDN gas supply onto site feeding a MAM owned and operated Medium Pressure (MP) gas meter rig.

There is a manufactured gas meter house at the main entrance to site inside the wire. There is a 2" steel EGDN riser into the meter rig and a 4" steel outlet feeding the MoD network.

There are no single supply meters on site.

The bulk fiscal meter is a twin stream meter fed at medium pressure by the EGDN network (Wales & West Utilities). This meter then supplies the MoD network at 30.7 mbar with two buildings (Tech Block and Navy Regional HQ building, one service riser) and one building (Main Building, below ground entry) fed from the MoD network.

MoD Network 01

Bulk Fiscal Meter – Schlumberger Delta D5 S/N – CD 33148 140 m/3hr MPRN – 50576006

Main Building

The gas enters the building via a 2" steel below ground entry. The ECV is located within an unlocked cupboard next to the main font doors. There is an external SIV for this service. The gas pipework continues in 2" steel and drops below ground on the outlet and feeds four appliances within the ground floor Galley and a single appliance within the basement.

Tech Block

The gas enters the building via a 3" steel riser. On building entry the gas runs through a low level MoD ECV and continues in 3" steel to feed two heating boilers.

Naval Regional HQ Building

The gas enters the building via a 25mm PE riser. The supply to the building is via installation pipework from the main building plantroom. On building entry the gas enters an understairs cupboard, through an AECV and secondary meter and runs to the single gas boiler in 22mm copper.

Secondary Meter – Parkinson Cowan Meter S/N – 0474754 S 6 m/3hr

The MoD network begins after the Bulk Fiscal meter outlet valve. The MoD is responsible from the Bulk Fiscal meter outlet valve up to and including the appliances in the buildings. There is one secondary gas meter on this site installed within the Navy Regional Office. The MoD network pipework is thought to have been installed in the mid 1990's. There is a mix of steel and PE pipe within the network.

Total Network Length – 159 metres

| 2.6 Primary N | Meter Deta | ails. | | | | | | | | | |
|---|-------------|-----------------------------|----------------------------|--------------------|----------------------------|------------------|----------------------------|--------------------|------------------------------|------------------|--------------------------------------|
| The following tak | ble describ | bes the | basic arrangen | nent of the | incoming primary | meter inst | allation(s). | (These are | the respon | nsibility of t | he MAM) |
| Number of prima | | | | 1 | <u> </u> | | | | | | |
| | | | | pipeline (resp | onsibility of the EGDN) | | Outlet | pipeline (respo | nsibility of the | MOD) | |
| Meter Name / ID | MAM Resp | | P tier – HP, IP, MP, LP | Pressure (mbar) | Material (EGDN Network) | Diameter (mm) | P tier – HP, IP, MP, LP | Pressure (mbar) | Material (MOD Network) | Diameter (mm) | Max Flow (M³ hr) |
| Bristol Flying Fox Bulk Fiscal Meter 01 | National | l Grid | MP | 1.94 bar | Steel | 50 | LP | 30.7 | Steel | 100 | 140 |
| | | | | | | | | | | | |
| 2.7 Utilisation | n Meters (| meters | supplied direct | ly from the | MOD gas networ | ·k) | | | | | |
| Utilisation Meter | Details ca | an be se | en in the GSM | P section | Α. | | | | | | |
| Number of utilisa installations: | ation mete | r | 1 | | | | | | | | |
| 2.8 Secondary | y Pressur | re Regu | lating Installa | tions (PRI | s). | | | | | | |
| The following take the consumers E | | bes the | basic arrangen | nent of the | PRIs. (This does | not include | utilisation | meter gove | rnors insta | illed downs | tream of |
| Number of PRI | | None | | | | | | | | | |
| installations: | | | | | | | | | | | |
| DDIA /15 | Ι. | | | | pipeline | | D.:: 145 | Outlet p | | | 16: 1 |
| PRI Name / ID | - ' | Nominal Reg size (mm) | P tier – MP, LP | Pressure (mbar) | Material (MOD Network) | Diameter (mm) | P tier – MP, LP | Pressure (mbar) | Material (MOD Network) | Diameter (mm) | Kiosk construction / condition |
| | | | | | | | | | | | |

2.9 Emergency Control Valves (ECVs).

The ECV(s) are included in the scope of the network and are therefore the responsibility of the MOD.

| \ / | the ECV(s) are included in the scope of the network and are therefore the responsibility of the MOD. | | | | | | | | |
|--------------------------------|--|--------------------------------------|----------------|-----------------------|---|---|------------------|--|-----------------------|
| The MOD gas networks at this e | 2 ECV's | | | | | | | | |
| Building Name / Number | Incoming Gas Pressure | Appliance / Process / Domestic | ECV No. / Code | Indoors / Outdoors | Key required to access the ECV – Where from? | ECV Location | Handle Fitted | ECV correctly labelled | Nominal Valve Size |
| Main Building | 30.7 | Catering & Hot water | WX15/ECV/001 | Indoors | No | Internal by main doors at point of entry | Yes | No – Labels to be installed before next annual review of this GSMP | 50 mm |
| Tech Block | 30.7 | Heating | WX15/ECV/002 | Indoors | Yes, Guard Room | Internal at point of entry to plant room | Yes | No – Labels to be installed before next annual review of this GSMP | 80 mm |

2.10 MOD Network Pipeline Details.

The table below shows the total pipeline lengths for the different pipe diameters and operating pressures

| operating pressures. | | | | | |
|----------------------|----------|-----------|---------------|-------------|--------|
| | Pressure | Pipe | Pipe | Number of | Total |
| Network Name / ID | (mbar) | Material | Diameter | Sections | Length |
| | | | (mm) | | (m) |
| Network 001 | 30.7 | PE | 125 | 1 | 59 |
| Network 001 | 30.7 | Steel | 80 | 1 | 3 |
| Network 001 | 30.7 | Steel | 50 | 1 | 4 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | Total ler | gth of all MO | D networks: | 66 m |

2.11 Network Interconnection.

The outlet pipework system from each of the primary meter installations can be isolated networks or may be interconnected with other MOD systems. For isolated systems turning off the gas supply at a single primary meter installation will shut off supply to all buildings / processes on that pipe system. Interconnected systems will require two or more primary meter installations to be turned off. Figures 2.1 and 2.2 below show the differences.

| The MOD pipework system on this e | Isolated | |
|-----------------------------------|----------|----------------------------|
| Supply from Primary Meter | Pressure | Can the interconnection be |
| (Name / ID) | (mbar) | isolated? |
| None | | |
| | | |
| | | |




Figure 2.1 – Isolated MOD pipework systems




Figure 2.2 – Interconnected MOD pipework systems

2.12 Sensitive and Critical Loads.

The MOD does not have any 'interruptible consumers. Historically large industrial / commercial consumers, who had an alternative fuel supply, could opt to pay a lower rate for an interruptible contract which enabled the supplier to isolate their supply at short notice in order to preserve the gas supply to the public and 'firm contract' industrial consumers in the event of a supply shortage.

However, all industrial and commercial supplies are, effectively, 'interruptible' isolation of these will usually be requested by the supplier in times of supply emergencies in order to preserve domestic supplies for as long as possible.

Where Industrial / commercial consumers have particularly sensitive or critical end users these can be taken into consideration by the EGDN when requesting isolation. Sensitive consumers could include supplies such as a school, medical facility, temperature-controlled ammunition stores etc.

| The number of sensitive loads at this | establishment is: | None | |
|--|---|---|--------------------------------|
| Facility / Consumers | Supplied from p | rimary meter | Approx. max |
| | name | / ID | throughput (m ³ hr) |
| None | | | |
| | | | |
| | | | |
| 2.13 Standby Alternative fuel Su | pplies. | | |
| Where operational critical supplies a should be considered which would e local or national supply emergency. | | | |
| Facility / Consumers | Supplied from primary meter name / ID | Approx. max throughput (m³ hr) | Alternative fuel supply |
| None | | | |
| | | | |

3 PLANT AND PREMISES

3.1 Drawings.

The gas layout drawings provide an overview of the gas network and the interfaces(s) with the EGDNs network.

The layout drawings should detail:

- a) The site boundaries.
- b) The primary meter installations.
- c) Secondary PRIs.
- d) Valve locations.
- e) Pipeline routes, diameters, material and depth.
- f) Operating pressure tier.
- g) Demarcations
- h) Responsibilities (EGDN / MOD)

The layout drawings are located at Annex B either embed as a PDF or hard copies. The drawings will be subject to the GRP quarterly review and following any physical changes or system updates. Hard copies of the drawings are located in the gas document centre.

| Gas Layout Drawing Number | Revision Date | Scale | Detail |
|---------------------------|------------------|--------|-------------------------|
| WX15-B-A1 | 30/11/2022 | 1:1000 | Site Gas Layout Drawing |
| | | | WX15-B-A1.pdf |

3.2 Additional Drawings.

In addition to layout drawings the below additional drawings are available from the gas documents centre and GRP.

| Additional Drawing Number | Revision Date | Scale | Detail |
|---------------------------|------------------|-------|--|
| WX15-A-A3 | 01/12/2022 | N/A | Not to Scale Main Building Gas Line Drawing |
| WX15-A-A3 | 01/12/2022 | N/A | Not to Scale Tech Block Gas Line Drawing |
| WX15-A-A3 | 01/12/2022 | N/A | Not to Scale Regional Naval HQ Gas Line Drawing |
| | | | WX15-A-A3.pdf |

3.3 Responsibility Interfaces and Access Arrangements.

For gas incidents or maintenance that affect the EGDN, the EGDN representative will become the network emergency controller. The EGDN establishment direct contact will be the GRP who will make all relevant arrangements for access to the primary meter(s) and plant room access (for emergency isolation etc).

As the MOD establishments are high security, all EGDN personnel who attend for gas supply emergencies or to carry out maintenance work will be granted access to site on an individual basis.

All EGDN personnel attending this establishment will be subject to site specific security procedures and will be required to be escorted whilst on site, access and escorting may vary depending on the nature of the visit, time of incident etc.

Below are the site-specific arrangements in place to allow the EGDN access during an emergency, as agreed by the HOE:

Guardroom on site – Guardroom is manned 24/7 – 01179 53 0869

4. OPERATION AND MAINTENANCE DOCUMENTATION

4.1 MOD Network Maintenance.

Network maintenance is mandated in GSMR and all network maintenance requirements and tasks on MOD establishments are detailed in the MOD Gas Network Technical Standard TS/GAS-01. TS/GAS-01 has been written in line with legislation, industry standards and guidelines.

The testing, inspecting and maintenance frequencies vary depending on the task, the table below shows the intervals at which it should be conducted and the date the tasks have been complete.

| TS/GAS- | N4 : | D: (D : () (T) | - . |
|--------------------------------------|--|---|---|
| | Maximum | Brief Description of Task | Task was |
| 01 | Interval | | completed |
| Job No. | Period | | on |
| 1 | General | | |
| 1.1 | 5 Years | Network Analysis – to model the adequacy of | 03/01/2023 |
| | | network design | |
| 1.2 | 5 Years | Network Validation Survey – to check network | 18/08/2022 |
| | | analysis model with measured data | |
| 2 | Iron Pipeli | nes, mains and services (includes buried outlet pig | ework from |
| | Primary M | eter Installations and PRIs.) | |
| | _ | · | |
| | Note: iron | pipes are not permitted for use with LPG – any such pi | ipes must be |
| | | y scheduled for replacement | • |
| 2.3 | 12 Month | FIM (or similar) leakage survey – Pipes within 30m of | N/A |
| | | a building | |
| 2.4 | 12 Month | Over line pipe survey – Pipes within 30m of a | N/A |
| | | building | |
| 2.5 | 5 Years | FIM (or similar) leakage survey – all pipe routes | N/A |
| | • • • • • • • • • • • • • • • • • • • | within site, regardless of proximity to buildings | ,, . |
| 2.6 | 5 Years | Over line pipe survey – all pipe routes within site, | N/A |
| 2.0 | o rouro | regardless of proximity to buildings | 1 4// (|
| 3 | Steel Pine | lines, mains and services (includes buried outlet pig | nework from |
| | | eter Installations and PRIs.) | |
| | · · · · · · · · · · · · · · · · · · · | otor motunations and riviory | |
| | | | |
| | Note: burie | ed steel nines are not permitted for use with LPG – an | v such nines |
| | | ed steel pipes are not permitted for use with LPG – an | |
| 3.1 | must be im | mediately scheduled for replacement, and the SME(Ga | s) informed |
| 3.1 | must be im | mediately scheduled for replacement, and the SME(Gallachard Cathodic Protection (CP) monitoring survey | s) informed N/A |
| 3.1 3.2 | must be im | mediately scheduled for replacement, and the SME(Gar Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes | s) informed |
| 3.2 | must be im 12 Month 12 Month | mediately scheduled for replacement, and the SME(Garanthodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings | s) informed N/A 13/05/2025 |
| 3.1 3.2 3.3 | must be im | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless | s) informed N/A |
| 3.2 | must be im 12 Month 12 Month 5 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 | must be im 12 Month 12 Month | mediately scheduled for replacement, and the SME(Garanthodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – | s) informed N/A 13/05/2025 |
| 3.2 3.3 3.4 | must be im 12 Month 12 Month 5 Years 5 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 | must be im 12 Month 12 Month 5 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 3.3 3.4 | must be im 12 Month 12 Month 5 Years 5 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 3.3 3.4 | must be im 12 Month 12 Month 5 Years 5 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 3.3 3.4 3.5 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years | mediately scheduled for replacement, and the SME(Ga: Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services with CP installed | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 3.3 3.4 3.5 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years | Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services | s) informed N/A 13/05/2025 13/05/2025 13/05/2025 N/A |
| 3.2 3.3 3.4 3.5 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years | Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services Leakage survey – All pipes within site regardless of | s) informed N/A 13/05/2025 13/05/2025 |
| 3.2 3.3 3.4 3.5 4 4.1 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years Polyethyle 5 Years | Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services with CP installed ene (PE) Pipelines, mains and services Leakage survey – All pipes within site regardless of proximity to buildings | s) informed N/A 13/05/2025 13/05/2025 13/05/2025 N/A |
| 3.2 3.3 3.4 3.5 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years | Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services with CP installed ene (PE) Pipelines, mains and services Leakage survey – All pipes within site regardless of proximity to buildings Over line pipe survey – All pipes within site | s) informed N/A 13/05/2025 13/05/2025 N/A |
| 3.2 3.3 3.4 3.5 4 4.1 | must be im 12 Month 12 Month 5 Years 5 Years 10 Years Polyethyle 5 Years | Cathodic Protection (CP) monitoring survey Leakage survey (where no CP installed) – pipes within 5m of buildings Leakage survey (where no CP installed) – regardless of proximity to buildings Over line pipe survey (where no CP installed) – regardless of proximity to buildings Close Interval Potential Survey (CIPS) – for buried pipelines, mains and services with CP installed ene (PE) Pipelines, mains and services Leakage survey – All pipes within site regardless of proximity to buildings | s) informed N/A 13/05/2025 13/05/2025 13/05/2025 N/A |

| 5 | This section | on refers to LPG installations only – refer to TS/GAS | 6-01 | |
|-----|--|--|------------|--|
| 6 | Secondary Pressure Regulating Installations (PRIs). | | | |
| | Note: this is for secondary network PRIs only – it does not include the PRIs associated with the Primary Meter Installation(s), first-stage LPG regulators or the Meter regulator(s) installed downstream of the consumers / user ECVs | | | |
| 6.1 | 12 Month | Functional check of PRI including safety / redundant systems | N/A | |
| 6.2 | 12 Month | Visual inspection of pipework within PRI housing | N/A | |
| 7 | Meter and PRI Housings Scope for this activity includes the housing of all meter and PRI installations | | | |
| 7.1 | 12 Month | Inspection of PRI housing (where present) | N/A | |
| 8 | Valves | | | |
| 8.1 | 12 Month | Inspection of valve chambers | 13/05/2025 | |
| 8.2 | 12 Month | Leakage detection survey within valve chamber | 13/05/2025 | |

4.2 Iron Pipework.

Where cast iron (including spun iron) or ductile iron pipework exists on an MOD establishment it is to be risk assessed in accordance with section 4.3 of the MOD GSC and, where required, entered into a mains replacement programme in order to comply with the UK mains replacement enforcement policy.

Below is the amount of Cast Iron and / or Ductile Iron pipe, and details, identified at this establishment from a survey:

| Cast Iron (m): | | Not Applicable | | | | |
|-------------------|----------|------------------------|--------|--------------|-------|-------------|
| Ductile Iron (m): | | | | | | |
| Pressure | Nominal | Cast Iron or | Total | Closet | Risk | Planned |
| (mbar) | Diameter | Ductile Iron | Length | Proximity to | Score | Replacement |
| | (") | (m) buildings (m) Date | | | | Date |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

5. RISK ASSESSMENTS

5.1 Model Risk Assessments.

The Model Risk Assessment (RA) shown in the table below, highlight the factors that will affect the safe management of the flow of gas, and the provision of the emergency response service. These RA, reviewed and modified as appropriate to this establishment, are shown at Annex C. (These RA must be reviewed and authorised by the GRP as being correct for this establishment with the date entered at the top of the RA).

| RA No. | Title (Model Risk Assessments) |
|--------|--|
| 1 | Any gas leak considered hazardous to persons or property (Under med/low pressure conditions). |
| 2 | Fire or explosion near to, or directly involving, a pipeline or gas facility. |
| 3 | A failure of operation of pipeline/plant onsite, or immediately downstream of site, that is maintained by the gas transporter. |
| 4 | A failure of operation of pipeline/plant onsite that is maintained by site services. |
| 5 | Failure of safety critical equipment. |
| 6 | Under-pressure in the gas system. |
| 7 | Over-pressure in the gas system. |
| 8 | Failure in system during load shedding. |
| 9 | General changes to the gas network. |
| 10 | Failure of PPM, general operation of the gas network plant/equipment and safety inspections. |
| 11 | Emergency Shutdowns. |
| 12 | Interface with Gas Transporter. |
| 13 | Interface with the consumers. |
| 14 | Interface with Emergency Services. |
| 15 | Natural Disasters, civil disturbances, other unforeseen events. |

5.2 Additional Site-Specific Risk Assessments.

In addition to the model RA shown above, the site-specific RAs shown below have been identified. These RA are shown in Annex D (As with the Model RAs above, these must be reviewed and authorised by the GRP as being correct for this establishment with the date entered at the top of the RA).

| | , |
|----|---|
| 16 | Buildings with steel tails on the service entries |
| 17 | |
| 18 | |
| 19 | |

6. SAFETY MANAGEMENT SYSTEMS

No site-specific considerations (refer to MOD Gas Safety Case Section 6) unless stated below:

Network maintenance will be undertaken by VIVO

7. EMPLOYEE COMPETENCE

No site-specific considerations (refer to MOD Gas Safety Case Section 7) unless stated below:

No additional site specific measures in place

8. CONTRACTORS

No site-specific considerations (refer to MOD Gas Safety Case Section 8) unless stated below:

No additional site specific measures in place

9. HEALTH AND SAFETY COMMUNICATION - INTERNAL

9.1 Health and Safety Communication

This section describes the systems in place to enable effective communications within this establishment. Different forms of communication are used to pass information to people within the MOD/MMOs depending on the type of information and the audience including in the event of an emergency.

9.1.1 Public Address System.

The public address arrangements for this establishment are shown below

There is no public address system on site

9.1.2 Internal Electronic Correspondence.

Details of any internal email or intranet correspondence are shown below

The site has the facility for email to be used for communication. Email addresses for Key site personalities are listed in section 1 of this document.

9.1.3 Direct Contact.

Details of any site-specific arrangements for direct MOD / MMO contact with site personnel and families are shown below

Face to face meetings with key personnel are possible on a regular basis if required.

9.1.4 Emergency Plans.

Details of any site-wide emergency plans and arrangements, including MMO documents are shown below

No specific gas emergency plan for the establishment is in place. MOD Exemplar Gas Safety Case to be used as guidance.

9.1.5 On-Site Emergency Services.

Details of site-specific arrangements for communication with site emergency services, such as fire, are shown below

There are no on-site emergency services. Site personnel will dial 999 for Police, Fire and Emergency Medical services.

For Gas Emergencies site will dial 0800 030 9320

10. HEALTH AND SAFETY COMMUNICATION - EXTERNAL

No site-specific considerations (refer to MOD Gas Safety Case Section 10) unless stated below:

No additional site specific measures in place

11. AUDITS

11.1 GSM Audit.

The audit process in place monitors and measures compliance with legislation and company policy and is aimed at ensuring the safe flow of gas within the MOD networks and downstream of the consumers ECV.

The GSM audit role is primarily concerned with assuring that the GRP duties are being effectively undertaken and that the gas risks are being effectively managed on the site. All GSM Audits will be carried out using the standard audit template prepared by the DIO PGE. Every site with gas networks shall be audited as frequently as practicable, ideally annually and in accordance with a programme agreed with the DIO PGE. Every site shall be audited at least once every three years. Each GSM shall implement an audit programme which must be agreed by the DIO PGE. All completed audit reports shall be sent to the DIO PGE for review and filing.

| As agreed with the PGE, GSM audits on this establishment will be carried out: | On a maximum three-yearly basis |
|---|---------------------------------|
| The last GSM audit was conducted on: | 15/07/2024 |

| The last GSM audit was carried out by: | Neville King |
|--|-------------------------------------|
| The qualitive assessment of the GSM audit concluded this establishment is: (safe to continue / safe to continue subject to caveats / unsafe to continue) | Safe to continue subject to Caveats |
| Audit findings: | See GSM report |
| Points addressed following last audit: | |

12. CO-OPERATION

12.1 Emergency Exercises.

On MOD networks, the MMO utilises EGDN to provide a gas emergency response service for dealing with reported gas escapes. However, the EGDN response would normally be to isolate MOD supplies at the incoming meter installation(s). As this is likely to cause considerable inconvenience and expense to MOD facilities, where possible MMO staff / contractors would attempt to attend the emergency in advance of the EGDN personnel to assess the emergency and advise EGDN accordingly.

It is the responsibility of the HoE to ensure that a gas emergency exercise is conducted on the establishment at least once in a three-year period. The HoE will require the support and involvement of the MMO and all key stakeholders such as the EGDN. Lessons learnt should be actioned and kept within the gas document centre.

| 3 | | | | | |
|--|---|--|--|--|--|
| Date of last emergency exercise: | No previous emergency exercises | | | | |
| Date of next planned emergency exercise: | From Q4 2022 | | | | |
| Date of last actual emergency involving | 17/01/2024 | | | | |
| EGDN: | | | | | |
| Were the EGDN involved in the last | N/A | | | | |
| emergency exercise: | | | | | |
| Were the MOD emergency services | No, there are no MoD emergency services on | | | | |
| involved in the last emergency exercise or | site. The gas RP was on site and the | | | | |
| actual emergency: | guardroom and site SHEF were involved and | | | | |
| | no evacuations were required, just a cordoned | | | | |
| | area externally. | | | | |
| Summary of lessons learnt from the last | None, procedures were correctly followed. | | | | |
| emergency exercise or actual emergency: | , | | | | |
| Date MMO emergency contact numbers | 17/01/2024 | | | | |
| and procedures were last tested: | | | | | |
| | | | | | |

13. EMERGENCY SERVICE RESPONSE TO GAS ESCAPES

No site-specific considerations (refer to MOD Gas Safety Case Section 13) unless stated below:

No additional site specific measures in place

14. INVESTIGATIONS

No site-specific considerations (refer to MOD Gas Safety Case Section 14) unless stated below:

No additional site specific measures in place

15. GAS QUALITY

No site-specific considerations (refer to MOD Gas Safety Case Section 15) unless stated below:

No additional site specific measures in place

16. CONTINUITY OF SUPPLY

No site-specific considerations (refer to MOD Gas Safety Case Section 16) unless stated below:

No additional site specific measures in place

17. ADEQUATE NETWORK PRESSURE

17.1 Network Analysis.

Network Analysis is the primary tool by which the MOD satisfies itself that anticipated levels of demand can be supplied from its MP and LP networks to gas consumers. It allows different scenarios to be examined. The technique ensures the efficient management and operation of the MP and LP gas supply systems. It enables a detailed understanding of the gas supply system to be developed upon which cost effective planning and operating decisions can be made.

In accordance with industry recommendations Network Analyses must be repeated at every site containing an MOD Network at least five-yearly, or sooner, if for gas system modification purposes or when demand profiles have changed, or are expected to change.

| For this establishment the network analysis was undertaken by: | DNV |
|--|------------|
| For this establishment the network analysis was undertaken on: | 03/01/2023 |

17.2 Design Minimum Pressure.

The MOD utilises nominal minimum design pressures, in compliance with IGE/GL/1. These minimum pressures will be seen at the extremities of the systems under extreme conditions. To ensure that all gas equipment downstream of the meter can be safely operated, it is a gas industry recommendation that the network should maintain a minimum of 20.75 mbar at the end of any service pipe. However, for existing networks, it is permitted to have a pressure as low as 19 mbar at the end of any service under 1 in 20 peak six-minute conditions. This value must also include any temporary contingencies to support maintenance activities. Where any appliances have elevated minimum recommended operating pressures (P_{ign}), the DmP must allow for this, taking into account any pressure losses across the meter (4mbar) and through installation pipework (10% of P_{ign}).

| The minimum modelled pressure (based on 1:20 peak 6 minutes flow conditions) at the outlet of the consumers ECV at the system extremity is: | 19 mbar |
|---|---------------|
| The location of the minimum pressure is: | Main Building |
| The declared minimum pressure (DmP) is: | 28.5 mbar |

17.3 Network Analysis Results.

A brief description of the network analysis results is below:

Pipe Data

The pipe model was built from the 'WX15-B-A1' file produced by DNV from DNV site surveys, supplied site drawings and utility line drawings where available. The files included the pipe lengths, connectivity, diameters and materials all used in the modelling.

Demand Data

The demand levels used in the analysis are the maximum estimated flows that the network is likely to experience. This criterion is stated in IGE/GL/1 Planning of Gas Distribution Systems of MOP not Exceeding 16 bar, section 4.2.1:

'Any system should be designed to meet the maximum demands placed upon it. Note: Experience has shown that this is likely to be the maximum demand that will occur in any period of not less than 6 minutes, expressed as an hourly rate.'

The Bristol Flying Fox CRFCA Network 01 supplies the Main Building, Tech Block and the Navy RHQ Building. The principal uses for gas are for space/water heating, and catering. The effects of diversity have not been considered. This undiversified demand modelling ensures that the worst-case scenario is assessed.

Details of installed appliances were available for all buildings on site. The appliance input ratings (kW) were used to calculate the peak instantaneous flow rates (sm3/h). These values represent the maximum flow within the pipe network and are undiversified values.

Supply Data

Gas is supplied to Bristol Flying Fox CRFCA from a medium pressure (MP) main. Supply pressure data obtained by DNV in the form of instantaneous pressure readings shows the outlet pressure of the main site regulators to be as follows:

• Network 01 Bulk Fiscal Primary Meter (BFPM), located in the Gas Meter House had an outlet pressure of 30.8 mbarg (standing).

This instantaneous pressure recorded at this meter has been used as the model operating pressure.

The capacity of the BFPM in the Gas Meter House is 142 sm3/h which is greater than the estimated maximum flow through the meter (89.9 sm3/h). This means that the main meter is adequately sized for the identified network appliances at maximum demand.

Conclusions

The pipe data available at the time of producing this report, and which has been used to build the Synergi network analysis model of Bristol Flying Fox CRFCA, was of a good quality.

Demands were estimated based upon appliance ratings determined during the site survey.

The BFPM has a greater capacity than the calculated maximum demand and is therefore adequately sized.

There is a reasonable degree of confidence in the pressures predicted by the network model.

Modelling of the documented infrastructure and maximum estimated gas demands shows that all the buildings modelled should receive gas with a pressure above the minimum limit of 19 mbarg within the network.

The results for the Bristol Flying Fox CRFCA model as a whole are satisfactory.

17.4 Network Validation Survey.

As part of the network analysis validation procedure, pressure monitoring points are to be installed on MOD networks to enable pressure surveys to be conducted. In accordance with the recommendations of Section 8.3.2. of IGE/GL/1, pressure surveys will need to be carried out on MOD networks to verify that the results from the network models were indicative of the recorded pressures on the network. This is a practice which is widely used throughout the gas industry to check network models provide realistic results.

It is the responsibility of the MMO to ensure adequate pressure surveys are conducted at regular intervals to validate the pressures predicted by network analysis results. This must be conducted at a minimum of once every five years, in conjunction with a Network Analysis or when demand profiles on the network have changed. Similarly, if the results of a previous Network Analysis are suspected to be inaccurate (for example, low extremity pressures being experienced), a repeat Network Analysis should be undertaken.

| For this establishment the latest validation | DNV |
|--|------------|
| survey was undertaken by: | |
| For this establishment the latest validation | 03/01/2023 |
| survey was undertaken on: | |

17.5 Network Validation Survey Results.

A brief description of the network validation survey results is below which includes a comparison of the modelled pressure and actual pressure record;

Pressure Survey

In accordance with the recommendations of Section 8.3.2 of IGE/GL/1, a pressure survey would normally be carried out on the Bristol Flying Fox CRFCA network in order to verify that the results from the network model were indicative of the recorded pressures on the network. This is a practice which is widely used throughout the gas industry to provide confidence in network analysis models.

The network was surveyed on the 18th August 2022. Single point pressure readings using a Druck pressure gauge or similar were recorded. These are attached to the outlet of the supply regulators and at the appliances in the buildings where possible.

A simple pressure survey of short-term single readings was undertaken at 2 meter/appliance in the modelled area. The recorded pressures taken in this type of survey may be standing pressures where the appliances are not operational, or working pressures, where they are. There may be several mbarg difference between these

Pressure Modelling and Comparison

The network model was built and analysed as detailed above. The pressure data collected during the survey was compared with the modelled pressures, as shown in the table below.

19 mbarg is used in this report as the minimum pressure requirement under maximum flow conditions for this network. This is taken as the pressure requirement for the inlet to the appliances. It is expected that the modelled pressures will fall below those recorded as the modelled demand is the estimated maximum and it is unlikely that these conditions were experienced whilst the survey was undertaken. Providing that the modelled pressures are not significantly lower than those recorded, or below the minimum pressure requirement, this should not be a cause for concern as the difference can be attributed to the lower demand flows being experienced.

| | Modelled Flow (sm³/h) | Pressure (mbarg) | |
|-------------------------------------|-----------------------------|------------------|----------|
| Building | | Single Read | Modelled |
| Network 01 | | | |
| Gas Meter House (BFPM) | | 30.8 (standing) | 30.8 |
| Main Building – Plant Room | 10.9 | 30.8 (standing) | 28.5 |
| Tech Block – Offices/Drill Hall | 75.7 | - | 30.1 |
| Navy Regional HQ Building - Offices | 3.2 | - | 29.5 |

All of the modelled pressures are similar to the recorded pressures as expected. As a result of the pressure comparison, there is a reasonable level of confidence in the modelling of the network.

The modelled network supplies each demand with gas above the minimum pressures of 19 mbarg.

The minimum modelled pressure on Network 01 is 28.5 mbarg at the inlet to the Main Building. This shows a modelled pressure drop of 2.3 mbarg from the supply (30.8 mbarg).

The results for the Bristol Flying Fox CRFCA model as a whole are satisfactory.

17.6 Corrective measures.

Following the network analysis and network validation survey the below corrective or mitigation measures have been planned at this establishment;

MOD network name / ID:

MoD Network 01

Consider the frequency at which network demands should be reviewed. IGE/GL/1 Section 8.2 Load Management, 8.2.1 states:

"The GT should have a policy and supporting procedures for allowing additional loads, and changes to loads, to be calculated."

Investigation into the use of the appliances in the network, with the possibility of further pressure and flow monitoring during the winter period.

18. GAS SUPPLY EMERGENCIES

No site-specific considerations (refer to MOD Gas Safety Case Section 18) unless stated below:

No additional site specific measures in place

19. GAS QUALITY - SOLE CONVEYER

No site-specific considerations (refer to MOD Gas Safety Case Section 19) unless stated below:

No additional site specific measures in place

20. DISCONTINUING GAS SUPPLY

No site-specific considerations (refer to MOD Gas Safety Case Section 20) unless stated below:

No additional site specific measures in place

21. RESTORATION OF SUPPLIES

No site-specific considerations (refer to MOD Gas Safety Case Section 21) unless stated below:

No additional site specific measures in place

ANNEX A

ANNEX A - ABBREVIATIONS

4C's Co-ordination, Co-operation, Communication and Control

AE Authorising Engineer

CI Cast Iron

CIPS Close Interval Potential Survey

CP Cathodic Protection

DI Ductile Iron

DIO SD EUS Defence Infrastructure Organisation Service Delivery, Energy, Utility and

Sustainability

DIO TS Defence Infrastructure Organisation Technical Services

DIO Defence Infrastructure Organisation

DmP Design Minimum Pressure ECV Emergency Control Valve

EGDN External Gas Distribution Network FIM Functional Independence Measure

GRP Gas Responsible Person

GSIUR Gas Safety (Installation and Use) Regulations1998

GSMR Gas Safety (Management) Regulations 1996

GSC Gas Safety Case GSM Gas Safety Manager

GSMP Gas Safety Management Plan

HoE Head of Establishment

HP High Pressure

IGEM Institute of Gas Engineers and Managers

IP Intermediate Pressure

LP Low Pressure

LPG Liquified Petroleum Gas MAM Meter Asset Manager

MMO Maintenance Management Organisation

MOD Ministry of Defence
MP Medium Pressure
NA Network Analysis
NG Natural Gas

NVS Network Validation Survey

PE Polyethylene

PGE Principal Gas Engineer

PRI Pressure Reduction Installation
PUS Permanent Under Secretary

RA Risk Assessment


SHEF Safety, Health, Environment and Fire

TLB Top Level Budget Holder

ANNEX B


ANNEX B - SITE LAYOUT DRAWINGS.

Site Gas network Layout Drawing




Gas Line Drawings

Main Building




C-2 Version 9.0 – 1st April 2021

Tech Block Plant Room



Regional Naval HQ



ANNEX C

ANNEX C - MODEL RISK ASSESSMENTS

| Site Reviewed Model Risk Assessment - 01 | | |
|---|---|--------------------------------|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| Any gas leak considered hazardous to persons or property Date reviewed: 18/02/2025 | | |
| Risk | Any leak at any pressure can be quantified as a hazard. The higher the pressure and/or depending on the location of the leak the risk to the surrounding area varies Depending on the severity of the leak, other hazards such as explosions, fires, supply failures, pollution and associated financial implications could arise Depending on how quickly & thoroughly the gas leak is dealt with the resulting hazards from the incident will vary. | |
| Caused By | Damage to pipelines from digging Failure of control equipment Damage caused by general construction Corrosion of pipelines Failure of mechanical joints and seals Deterioration or rupture of pipeline Poor communication between involved parties can exacerbate the problem Length of response time by first responders | |
| Hazards Resulting from Risk | Damage to pipelines caused by uncontrolled escaping gas Risk of causing a supply emergency Damage to persons & property Risk of Explosions & Fire Pollution of environment Purging maybe required after corrective action | |
| Current Preventative Methods | Permits to Dig Planned Preventative Maintenance Type & Quality control of materials used in gas network Strict adherence to emergency procedures in the event of an emergency Isolation via emergency stops Installation of gas network to industry standards | |
| Further Required Preventative Methods | Pressure monitoring More accurate gas network layout drawings Use of the gas safety management plan Training of all involved parties Training and simulated gas emergency drills | |
| Audits | In the event of an incident, near miss or any other hazardou must be reviewed and updated as appropriate. | is occurrence this RA |

| Site Reviewed Model Risk Assessment - 02 | | | |
|--|---|--------------------------------|--|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert | |
| Fire or explo | osion near to, or directly involving, a pipeline or gas facility | Date reviewed: 18/02/2025 | |
| Risk | Any fire or explosion directly involving a gas pipeline or f major incident. Any fire or explosion near to a gas pipeline or facility ma and or damage to property. | , | |
| Caused By | Undetected trapped gas Unresolved gas leaks Failure of control equipment, pipelines, seals, joints etc. Damage to gas pipelines through digging and/or general construction Incorrect initial procedure when dealing with a gas leak Inadequate action by first responder | | |
| Hazards Resulting from Risk | Fire and/or explosions causing death and/or injury to ger Damage and/or destruction of surrounding properties Damage to gas pipelines, gas control centres & other ga Disruption of gas supply Secondary Explosions & Fire resulting from inaction | | |
| Current Preventative Methods | Scheduled Maintenance Designed for purpose Permits to Dig Strict adherence to emergency procedures, including verarea | ntilating and evacuating | |
| Further Required Preventative Methods | Pressure monitoring Use of the gas safety management plan Training and simulated gas emergency drills | | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | dous occurrence this RA | |

| Site Reviewed Model Risk Assessment - 03 | | |
|--|--|---|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| | A failure of operation of pipeline/plant onsite, or immediately downstream of site, that is maintained by the EGDN | |
| Risk | Any incident directly involving the medium pressure pipe dealt with by Wales and West Utilities in the event of a least by Wales and West Utilities has an impact on the severit The level of cooperation and communication between Exparties has an impact on the eventual severity of the incident | eak the response time by of the incident GDN and the onsite |
| Caused By | Poor response time by Wales and West Utilities Poor communication between onsite parties and Wales and West Utilities Poor coordination of onsite parties and Wales and West Utilities Poor communication of procedures Lack of supply resulting in drop in supply pressure, resulting in site wide gas supply failure | |
| Hazards Resulting from Risk | Disruption of gas supply to whole site Re-commissioning & purging after corrective action Re-ignition of non-automatic ignition systems Long down time due to above hazards | |
| Current Preventative Methods | General communication between site and Wales and We | est Utilities |
| Further Required Preventative Methods | Communication of site procedures to Wales and West U Understanding Wales and West Utilities procedures Training and simulated gas emergency drills Training for quicker response time Pressure monitoring Planning for load shedding (reduces the risk of site wide Fitting automatic ignition systems as standard Use of the gas safety management plan | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 04 | | |
|--|--|---|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| A failure of o | A failure of operation of pipeline/plant onsite that is maintained by site services | |
| Risk | Any incident directly involving the low or medium pressu be dealt with by the onsite gas operatives. In the event of time by the onsite operatives has an impact on the sevent. The level of cooperation and communication between or emergency services and gas operatives has an impact of the incident. | of a leak the response rity of the incident nsite parties such as |
| Caused By | Poor response time by site services Poor communication between onsite parties Poor coordination of onsite parties Poor communication of procedures | |
| Hazards Resulting from Risk | Disruption of gas supply to whole site Re-commissioning & purging after corrective action Re-ignition of non-automatic ignition systems Long down time due to above hazards | |
| Current Preventative Methods | Scheduled Maintenance Designed for purpose Permits to Dig Strict adherence to emergency procedures | |
| Further Required Preventative Methods | Pressure monitoring Use of the gas safety management plan Training and simulated gas emergency drills Training for quicker response time Planning for load shedding (reduces the risk of site wide gas failure) Fitting automatic ignition systems as standard | |
| Audits | In the event of an incident, near miss or any other hazard must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 05 | | | |
|--|---|---------------------------|--|
| For: HMS Flyi | For: HMS Flying Fox RNR ARC ACF SCC | | |
| | Failure of safety critical equipment Date reviewed: 18/02/2025 | | |
| Risk | Failure of safety critical equipment can have a severe im gas network. | pact on the safety of the | |
| Caused By | Lack of/or poor maintenance Incorrect use of equipment Ageing equipment | | |
| Hazards Resulting from Risk | Lack of control over gas network, resulting in a gas incident Lack of control over gas network during a gas incident | | |
| Current Preventative Methods | Scheduled Maintenance Designed for purpose Regular operational training | | |
| Further Required Preventative Methods | Pressure monitoring Further training of gas operatives Replacing old equipment where required | | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | dous occurrence this RA | |

| Site Reviewed Model Risk Assessment - 06 | | |
|--|--|---|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| III. III. III. III. III. III. III. III | | Date reviewed: 18/02/2025 |
| Risk | If at any point the pressure in a gas network drops below safety regulators will stop the flow of gas. These regulate appliances and in some instances will also be downstreat individual houses. There is also a regulator on the main. If the pressure in a gas network, leading into a house or certain level a gas safety regulator will terminate the flow the pilot lights to be extinguished. On this site, due to the and houses, it may take up to 3 days to re-ignite all the second control of the same points. | ors are fitted to gas am of the gas meter into intake to the site. facility, drops below a of gas. This will cause multitude of buildings |
| Caused By | Gas leaks Poor gas network management Failure of Compressors Inadequate supply of gas in the system Failure of pressure control system | |
| Hazards Resulting from Risk | Loss of gas supply Gas safety regulators being tripped (requires manually remodels) Long recovery period Potential for air in the gas network | esetting on older |
| Current Preventative Methods | Scheduled Maintenance Designed for purpose Network Analysis and Validation | |
| Further Required Preventative Methods | Pressure monitoring Regular training of gas operatives Replacing old equipment where required Fitting automatic ignition systems as standard Replacing manual gas safety regulators with automatic of | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 07 | | |
|--|---|--------------------------------|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| | | Date reviewed: 18/02/2025 |
| Risk | If at any point the pressure in a gas network climbs above a certain level, gas safety regulators will stop the flow of gas. These regulators are fitted to gas appliances and in some instances will also be downstream of the gas meter into individual houses. There is also a regulator on the main intake to the site. If the pressure in a gas network, leading into a house or facility, climbs above a certain level a gas safety regulator will terminate the flow of gas. This will cause the pilot lights to be extinguished. On this site, due to the multitude of buildings and houses, it may take up to 3 days to re-ignite all the systems. | |
| Caused By | Failure of pressure control system Incorrect pipe/valve sizing Blockages in system Poor gas network management | |
| Hazards Resulting from Risk | Rupture of gas pipes due to high pressure related Damage to valves and other control equipment Damage to seals and joints Loss of gas supply | |
| Current Preventative Methods | Scheduled Maintenance Designed for purpose | |
| Further Required Preventative Methods | Pressure monitoring Regular training of gas operatives Use of the gas safety management plan Maintenance Regime | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 08 | | |
|--|---|--------------------------------|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| | Failure in system during load shedding | Date reviewed: 18/02/2025 |
| Risk | In the event of a gas supply emergency, load shedding can be used to stabilise the pressure in the system. However, if a section is isolated and the consumers on that branch use their gas supply the pressure in that branch will drop below acceptable levels and the pressure safety regulators will trip | |
| Caused By | Insufficient communication between onsite parties and the end user Insufficient means of monitoring pressure | |
| Hazards Resulting from Risk | Loss of gas supply Gas safety regulators being tripped (requires manually resetting on older models) Long recovery period Potential for air in the gas network | |
| Current Preventative Methods | Maintenance Regime Written Procedures Use of Gas Safety Management Plans Communication between MMO and GRP | |
| Further Required Preventative Methods | Better communication Pressure monitoring Use of the gas safety management plan Fitting automatic ignition systems as standard Replacing manual gas safety regulators with automatic of | cut-outs |
| Audits | In the event of an incident, near miss or any other hazard must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 09 | | |
|--|--|--------------------------------|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert |
| | General changes to the gas network | Date reviewed: 18/02/2025 |
| Risk | If during the design phase the sizing of the system is under/oversized, it could result in under/over pressure scenarios. If during the installation of a gas network, the work is not carried out to the relevant British Standards and if the work is not undertaken by operatives trained and skilled to the same British Standards, failure may take place. | |
| Caused By | Incorrect pipe sizing at design phase Underestimating impact on overall site gas supply Incorrect installation of plant and pipelines Under qualified gas operatives used for gas works | |
| Hazards Resulting from Risk | Damage to pipelines and gas network plant and equipment Risk of causing a supply emergency Damage to persons & property Risk of Explosions & Fire | ent |
| Current Preventative Methods | Using trained individuals to carry out work to the gas net Checking credentials of design authority for gas network Use of Qualified Designers | |
| Further Required Preventative Methods | Monitoring competence of gas network operatives Use of the Gas Safety Management Plan Further checking/commissioning of completed works | |
| Audits | In the event of an incident, near miss or any other hazard must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 10 | | | |
|--|--|--------------------------------|--|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert | |
| | Failure through PPM, general operation of the gas network plant/equipment and safety inspections | | |
| | Inadequate action during maintenance can cause failure | in the system | |
| | If safety inspections are not carried out regularly, the system may be vulnerable to failure | | |
| Risk | The day-to-day operation of the system is vital to the over gas network. If the day-to-day operation is not undertake the gas network could be vulnerable to failure | | |
| | Gas plant & pipelines are not sufficiently maintained | | |
| | Scheduled activities do not take place. | | |
| | Operatives are insufficiently trained | | |
| 0 | Inadequate co-ordination of operation | | |
| Caused By | Inadequate communication between onsite parties | | |
| | Inadequate planning of scheduled activities | | |
| | Inadequate inspection and testing of equipment | | |
| | | | |
| | Damage to pipelines and gas network plant and equipment | | |
| Hazards | Risk of causing a supply emergency | | |
| Resulting | Damage to persons & property | | |
| from Risk | Risk of Explosions & Fire | | |
| | Monitored and maintained | | |
| | Using trained individuals to carry out work to the gas net | work | |
| Current | Following PPM schedules to carry out works | | |
| Preventative Methods | Awareness Training, drills and exercise | | |
| Wethous | Using qualified operatives | | |
| | Monitoring competence of gas network operatives | | |
| | Checking credentials of design authority for gas network | redesign | |
| Further | Employ better lines of communication between parties | | |
| Required Preventative | Compliance with the Gas Safety Management Plan | | |
| Methods | | | |
| | | | |
| | | | |
| Audits | In the event of an incident, near miss or any other hazar | dous occurrence this RA | |
| | must be reviewed and updated as appropriate. | | |

| Site Reviewed Model Risk Assessment - 11 | | |
|--|---|------------------------------|
| For: HMS Flyi | For: HMS Flying Fox RNR ARC ACF SCC | |
| | Emergency Shutdowns | Date reviewed: 18/02/2025 |
| Risk | Emergency shutdowns can be used in the event of a gas warrants the gas network or part thereof to be shut down can have a severe impact on the resolution of the incider | n. If this process fails, it |
| Caused By | Failure of emergency shutdown valves Ageing emergency shutdown valves Lack of sufficient facilities for segregated shutdowns | |
| Hazards Resulting from Risk | Escalating hazard cause by existing emergency Damage to pipelines and gas network plant and equipment Risk of causing a supply emergency Long down time | ent |
| Current Preventative Methods | Communication Between all Parties Written Procedures and Permits Required Work Carried out to Regulatory Standards | |
| Further Required Preventative Methods | Use of the Gas Safety Management Plan Providing strategically placed emergency shutoff valves Scheduled PPM Checking credentials of design authority for gas network Replacing old equipment where required | redesign |
| Audits | In the event of an incident, near miss or any other hazard must be reviewed and updated as appropriate. | dous occurrence this RA |

| Site Reviewed Model Risk Assessment - 12 | | | |
|--|--|--------------------------------|--|
| For: HMS Flying Fox RNR ARC ACF SCC | | Accepted by: Jason Cuthbert | |
| | Interface with Gas Transporter Date reviewed: 18/02/2025 | | |
| Risk | If interfaces between the site team and the gas transporter carefully, the fallout from gas incidents can become more process. | • | |
| Caused By | Poor response time by EGDN Poor communication between onsite parties and EGDN Poor coordination of onsite parties and EGDN Poor communication of procedures | | |
| Hazards Resulting from Risk | Damage to pipelines Resultant hazards from any gas incident can escalate Risk of causing a supply emergency Damage to persons & property Risk of Explosions & Fire | | |
| Current Preventative Methods | MMO Call Centre Number to be Used All GSM's and GRP's will be aware of any calls to EGDN | | |
| Further Required Preventative Methods | Communication of site procedures to EGDN Understanding EGDN procedures Training and simulated gas emergency drills Regular communication through fixed procedures | | |
| Audits | In the event of an incident, near miss or any other hazardou must be reviewed and updated as appropriate. | s occurrence this RA | |

| Site Reviewed Model Risk Assessment - 13 | | | | |
|--|---|--------------------------------|--|--|
| For: HMS Flying Fox RNR ARC ACF SCC | | Accepted by: Jason Cuthbert | | |
| Interface with Consumer | | Date reviewed: 18/02/2025 | | |
| Risk | If communication between the site team and the end user are not carefully established, the fallout from gas shortages could result in the system having to be purged and the pilot lights re-ignited. On a large site such as this, it could take up to three days to re-ignite all pilot lights. | | | |
| Caused By | Poor communication Lack of understanding No method of checking on gas usage | | | |
| Hazards Resulting from Risk | Risk of causing a supply emergency Loss of pressure in system Long recovery period Potential for air in the gas network | | | |
| Current Preventative Methods | Communication between all Parties Written Procedures and Permits Required | | | |
| Further Required Preventative Methods | Pressure monitoring system Use of the Gas Safety Management Plan | | | |
| Audits | In the event of an incident, near miss or any other hazardou must be reviewed and updated as appropriate. | s occurrence this RA | | |

| Site Reviewed Model Risk Assessment - 14 | | | | |
|--|--|--------------------------------|--|--|
| For: HMS Flying Fox RNR ARC ACF SCC | | Accepted by: Jason Cuthbert | | |
| Interface with Emergency Services | | Date reviewed: 18/02/2025 | | |
| Risk | The first responder has a duty to minimise the risk to the surrounding area upon arrival. If the gas incident is within an enclosed area, isolating the system is the correct course of action. However, in a open, well ventilated area, isolating the system may not be necessary, and could cause secondary hazards | | | |
| Caused By | Poor communication Lack of understanding | | | |
| Hazards Resulting from Risk | Risk of causing a supply emergency Causing the need to purge systems Long downtime of gas network | | | |
| Current Preventative Methods | GRP will be aware of any gas incidents on site GRP to manage gas incidents and communicate with sit | e and EGDN FCO | | |
| Further Required Preventative Methods | Providing training to the Emergency Services, so that the tackle gas incidents | ey will be able to better | | |
| Audits | In the event of an incident, near miss or any other hazar RA must be reviewed and updated as appropriate. | dous occurrence this | | |

| Site Reviewed Model Risk Assessment - 15 | | | | |
|---|---|--------------------------------|--|--|
| For: HMS Flyi | ng Fox RNR ARC ACF SCC | Accepted by: Jason Cuthbert | | |
| Natural Disasters, civil disturbances, other unforeseeable events | | Date reviewed: 18/02/2025 | | |
| Risk | The risk of unforeseeable events causing gas related incidents cannot be planned for. However, it is possible to minimise the impact of the resulting hazards | | | |
| Caused By | Explosions Ground tremors Gas pipe sabotage | | | |
| Hazards Resulting from Risk | Damage to pipelines caused by uncontrolled escaping gas Risk of causing a supply emergency Damage to persons & property Risk of Explosions & Fire Pollution of environment Purging maybe required after corrective action | | | |
| Current Preventative Methods | High security levels GRP will be aware of any gas incidents on site GRP to manage gas incidents and communicate with site and EGDN FCO | | | |
| Further Required Preventative Methods | Use of the Gas Safety Management Plan | | | |
| Audits | In the event of an incident, near miss or any other hazar must be reviewed and updated as appropriate. | rdous occurrence this RA | | |

ANNEX D

ANNEX D - ADDITIONAL SITE-SPECIFIC RISK ASSESSMENT TEMPLATE

Please copy and add further sheets as required

| Additional Site-specific Risk Assessment 16 | | | | |
|---|--|--------------------------------|--|--|
| For: HMS Flying Fox RNR ARC ACF SCC | | Accepted by: Jason Cuthbert | | |
| Buildings with steel tails on the service entries | | Date reviewed: 18/02/2025 | | |
| | Uncontrolled gas escape | | | |
| Risk | | | | |
| Kisk | | | | |
| | | | | |
| | Corrosion of steel tails | | | |
| | Failure of vulnerable pipework as a result of third party interference | | | |
| Caused By | | | | |
| | | | | |
| | | | | |
| | Loss of gas supply | | | |
| | Long recovery period | | | |
| Hazards | Re-commissioning & purging after corrective action | | | |
| Resulting | Re-ignition of non-automatic ignition systems | | | |
| from Risk | Damage to persons & property | | | |
| | Risk of Explosions & Fire | | | |
| | Pollution of environment | | | |
| | Over line and leakage surveys | | | |
| Current | Installation of gas network to industry standards | | | |
| Preventative | Type & Quality control of materials used in gas network Strict adherence to emergency procedures in the event of an emergency | | | |
| Methods | hods Sinct adherence to emergency procedures in the event of an emergency | | | |
| | | | | |
| | Vulnerable pipework surveys and corrective actions | | | |
| | Replacement of steel tails where required and when other modifications of the | | | |
| Further | infrastructure are taking place | | | |
| Required | Ŭ. | | | |
| Preventative | | | | |
| Methods | | | | |
| | | | | |
| | | | | |
| Audits | In the event of an incident, near miss or any other hazardou | s occurrence this RA | | |
| Audits | must be reviewed and updated as appropriate. | | | |