

Project Number 2481

Management Asbestos Survey Report

Lawrence Weston Platoon, **Bristol, BS11 ONT**



Working in Partnership with Shield Environmental Services Shield



Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	1



Contents

Section	
1	Contacts & Authorisation
2	Executive Summary
3	Site Description & Survey Information
4	Positive and Presumed Photos Sheets
5	Negative Photos Sheets
6	Survey Objectives
7	Survey Techniques
8	Survey Caveat
9	Survey Notes
10	Material Assessment Algorithm
11	Certificates of Bulk Analysis
12	Site Plan

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	2



Section 1: Contact Details

Client Details:		Instructing Party:		
Wessex RFCA Mount House Mount Street		Shield Environmental Shield House Caxton Business Park		
Taunton TA1 3QE		Crown Way Bristol BS30 8XJ		
Contact Name:	Sue Morrell	Contact Name:	Chloe Smith	
Tel: 01823250115	Fax: N/A	Tel: 01173012650	Fax: N/A	

Site Address: Lawrence Weston Platoon Bristol BS11 0NT		Report Author: Armour Analytical Services Admirals Yard Station Road Bristol BS34 6LR	
Contact Name:	Nick Broderick	Contact Name:	David Kelly
Tel: 07786984823	Fax: N/A Mobile: 07769707519		7519

Lead Surveyor's Name:	Lead Surveyor's Authorising Signature:
D. Kelly	Belly

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	3



Section 2: Executive Summary

Sample Number	Sample Type	Location	Analysis
DK/1	Floor Tiles, Adhesive and Debris	External - Concrete Base	Chrysotile
DK/2	Damp Proof Course to concrete base	External - Concrete Base	N.A.D.I.S

N.A.D.I.S – No Asbestos Detected in Sample A.D – Asbestos Detected

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	4



Section 3: Site Description & Survey Information

Brief description on the general building construction

Timber frame construction with a pitched felt roof.

Caveat for no access areas

N/A

EXTERNAL MATERIALS	
Roof Type	Pitched
Roof Materials	Felt
Soffits	N/A
Fascia	Timber
Walls	Timber
Verge Under cloaking	N/A
Guttering	Plastic
Downpipes	Plastic
Window/Door frames	UPVC
Other Materials	Floor tiles and adhesive debris to external of
	building
INTERNAL MATERIALS	
Loft Insulation	Fiberglass
Roof Underlining	N/A
Ceilings	Plasterboard
Walls <i>Internal</i>	Plasterboard
Floors	Tiles, Lino, Timber, Carpet
Doors/Frames	Timber
Pipework/Insulation	Copper
Boxings	N/A
Boiler Make	Modern water heater
Flue Pipes	N/A
Storage Heaters	Modern electric heaters
Electrical Boxes/Machinery	Modern
Ducting/Risers	N/A
Stairs	N/A
Lift Shafts	N/A
Other Materials	N/A

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	5



Section 4: Positive and Presumed Photos Sheets

Item No: 1 Sample No: DK/1

Location: External – Concrete Base





Material Description:	Floor Tile and Adhesive debris on floor		
-			
Identification:	Sampled – Asbestos Dete	ected	
Approx. quantity:	12M2 of Adhesive 1-2M2 o	f Tiles	
Accessibility	Medium	Assessment Score	
Product type:	Composite	1	
Extent of Damage:	Major 3		
Surface Treatment:	Non-Friable 0		
Asbestos type:	Chrysotile 1		
	Material Assessment Score:	4	
Priority Assessment Score: Negligible			
Action:	Manage/Remove Debris		
Comments:	N/A		


Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	6



Section 5: Negative Photos Sheets

Item No: 2 Sample No: DK/2

Location: External – Concrete Base





Material Description:	Damp Proof Course to C	Damp Proof Course to Concrete Base		
Identification:	Sampled – No Asbesto	os Detected		
Approx. quantity:	6LM	6LM		
Accessibility	N/A	Assessment Score		
Product type:		N/A		
Extent of Damage:		N/A		
Surface Treatment:		N/A		
Asbestos type:		N/A		
	Material Assessment Score:	N/A		
	Priority Assessment Score:	N/A		
Action:	N/A			
Comments:	N/A			

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	7



Item No: 3 Sample No: N/A

Location: Lobby





Material Description:	Visual Inspection – No Suspe	Visual Inspection – No Suspect Materials Found			
Identification:	N/A				
Approx. quantity:	N/A				
Accessibility	N/A	Assessment Score			
Product type:		N/A			
Extent of Damage:	N/A				
Surface Treatment:		N/A			
Asbestos type:		N/A			
	Material Assessment Score:	N/A			
Priority Assessment Score: N/A					
Action:	Action: N/A				
Comments:	N/A				

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	8



Item No: 4 Sample No: N/A

Location: WC's x 2





Material Description:	Visual Inspection – No Suspe	ct Materials Found		
Identification:	N/A	N/A		
Approx. quantity:	N/A			
Accessibility	N/A Assessment Sco			
Product type:		N/A		
Extent of Damage:		N/A		
Surface Treatment:		N/A		
Asbestos type:		N/A		
	Material Assessment Score:	N/A		
	Priority Assessment Score: N/A			
Action:	Action: N/A			
Comments:	N/A			

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	9



Item No: 5 Sample No: N/A

Location: Store





Material Description:	Visual Inspection - No Suspe	ct Materials Found	
Identification:	N/A		
Approx. quantity:	N/A		
Accessibility	N/A Assessment Scor		
Product type:	N/A		
Extent of Damage:	e: N/.		
Surface Treatment:		N/A	
Asbestos type:		N/A	
	Material Assessment Score:	N/A	
	N/A		
Action:	N/A		
Comments:	Modern electrics and w	ater heater	


Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	10



Item No: 6 Sample No: N/A

Location: Classroom





Material Description:	Visual Inspection – No Suspe	ct Materials Found	
Identification:	N/A		
Approx. quantity:	N/A		
Accessibility	N/A Assessment Scor		
Product type:	N/A		
Extent of Damage:		N/A	
Surface Treatment:		N/A	
Asbestos type:		N/A	
	Material Assessment Score:	N/A	
	Priority Assessment Score:		
Action:	N/A		
Comments:	Comments: N/A		

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	11



Section 6: Survey Objectives

Instructions were received from Sue Morrell of Wessex RFCA to carry out a Management asbestos survey at Lawrence Weston Platoon, Bristol, BS11 0NT in accordance with HSG264 and Armour Analytical's quality procedures.

The survey was carried out on 20^{th} September 2019 by David Kelly with the objective of facilitating a Management report.

This Management survey is characterised as a 'Visual Inspection Sampling and Identification Survey' in HSG264. This type of survey is used to locate and describe, so far as is reasonably practicable, all asbestos containing materials (ACMs) in the building and will by its nature involve the partial destruction of the building's fabric as access is gained to all areas. A full sampling programme is undertaken to identify possible ACMs and estimate the extent of ACMs reported.

The objective of this survey report is to identify, so far as is reasonably practicable, the location, extent, product type and composition of ACMS within the building to enable the building occupants to put management and remedial procedures in place.

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	12



Section 7: Survey Techniques

Each floor, room and area within the scope was systematically inspected for suspect materials thought or known to contain asbestos and where such materials were encountered their location, extent, and composition were recorded.

Where materials of a similar nature exist, to those previously sampled, and a reasoned argument can be made that their composition is likely to be identical further physical sampling was not undertaken.

Photographs were taken of all sample locations, unless otherwise stated.

The analysis of suspect ACMs was undertaken by a UKAS accredited laboratory using the analytical method detailed in *HSG248*, *Appendix 2 -Asbestos: The analysts' guide for sampling, analysis and clearance procedures.*

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	13



Section 8: Survey Caveat

This report is based upon a management report inspection of an unfamiliar site. During the course of the survey all reasonable efforts were made to identify the physical presence of materials containing asbestos within the building.

A Management Survey is a non-intrusive survey, meaning that access within the fabric of the building is limited. The survey does not include access to the following areas (unless agreed beforehand with the Client and provisions are put in place):

- Within wall or ceiling construction;
- Under fixed flooring;
- Within non-openable boxings;
- Within live electrics, boilers or machinery;
- Where access/visibility is limited in an area due to stored items, furniture or services;
- Areas where there is no safe access to inspect such as floor ducts, lift shafts and loft spaces with no crawlboards;
- High level areas that are too high to safely inspect.
- Within pipework insulation throughout building as this would affect the integrity of services.

Any intrusive works carried out within the building must first be subject to a Refurbishment Asbestos Survey.

This report will be restricted to the areas that fall within the scope of works for project and will not take into account any area's that do not fall within the scope. Any asbestos that is identified within this report will need to be added to the buildings existing information and should not form the basis for a management survey. This survey will not include priority assessments nor will it include a register.

This survey considered the construction of the building, associated fixtures & fittings and associated structures and in no way should it be considered as a ground investigation report.

Services should be disconnected prior to commencement of a Management survey; however, where plant and/or electrical installations are live or appear to be live then these will not be accessed.

This survey report is not a bill of quantities.

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	14



Section 9: Survey Notes

This report has been written with reference to the various Guidance Notes etc, issued, and current at the date of this report and describes circumstances at the site on the date the investigation took place.

Where similar items exist in the building, only one or two samples have been taken to ascertain the material content. It was assumed that similar products were of the same material.

Any person undertaking work within the buildings should be told of the presence of asbestos. This briefing also applies to any other person associated with the site, including staff, subcontractors and others.

The drawings in the report are not to scale and are illustrative only to indicate approximate locations. The descriptions used are for location identification purposes.

All the recommendations described in this report are based upon assumptions made after consideration of the type of material, condition of the material, its location, analysis result and type of use the area is thought to be subjected to. However, statutory authorities or others could require amendments based on local knowledge, change in legislation, change in use or indeed other conditions or criteria.

Samples taken from floor tiles (or similar material) may include a bitumen adhesive as part of the sample. It is known that some proprietary brands of bitumen have an asbestos content and this will be included as an integral part of the bulk sample unless otherwise stated.

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	15



Section 10: Material Assessment Algorithm

Variable	Score	Examples
Installation / Product type	1	Vinyl, 'Bakelite', Cement
-7/1-1	2	Asbestos insulating board, paper, rope
	3	Pipe insulation, spray coating, friable debris
Condition / damage	0	Good
	1	Slight / minor damage
	2	Moderate damage – breakage to surface treatment
	3	Major damage – smashed or exposed material
Surface treatment	0	Non-friable e.g. vinyl
	1	Enclosed insulation, encapsulated AIB
	2	Unsealed AIB, encapsulated insulation
	3	Unsealed insulation or spray coating
Asbestos type	1	Chrysotile
	2	Amosite & other amphiboles
	3	Crocidolite

The scores from each of the four sections are added together to produce a risk score:

Risk score	Risk assessment
10 or more	High risk
7 – 9	Medium risk
5 – 6	Low risk
4 & below	Negligible risk

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	16



Section 11: Certificates of Bulk Analysis



Our Ref: J176053 FI: 2

Your Ref: Date: 25/09/2019

ENVIROCHEM

Analytical Laboratories Ltd. 12 The Gardens Broadcut, Fareham Hampshire PO16 8SS



Fax: (01329) 287755 www.envirochem.co.uk office@envirochem.co.uk

Asbestos Fibre Identification Report

Client: Armour Analytical Services Ltd

Admirals Yard, Station Road, Patchway, Bristol, BS34 6LR

Site Address: Lawrene Western, Platoon, Bristol, . Armour Analytical Services Ltd Sampled By:

Date sampled/received: 24th September 2019 Date analysed: 25th September 2019 Analyst/s: Raphael Mirzaians

12 The Gardens, Broadcut, Fareham, Hampshire, PO16 8SS Analysis Location:

ANALYTICAL PROCEDURE

Fibre identification was carried out in accordance with the documented 'in-house' methods based on the HSE Guidance Note HSG 248. These employed stereo microscopy, polarized microscopy and dispersion staining techniques.

RESULTS

Sample No.	Sample Ref.	Location	Asbestos Detected	Asbestos Type
1	BS576488	External - Concrete Base - Floor Tiles, Adhesive and Debris	Yes	Chrysotile
2	BS576489	External - Concrete Base - Damp Proof Course to concrete base	No	



Authorised signatory PRINT NAME: Frances Scott

Reg. No. 2378228 England. Registered Office: Envirochem, 12 The Gardens, Broadcut, Fareham, Hampshire, PO16 8SS. Page 1 of 1

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	17




KEY

Visual Inspection

No ACM's Detected

No Access

Section 12: Site Plan



Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	18



I the surveyor can confirm that this report is accurate to my findings onsite and this survey has been Content checked by myself.

Checked by: David Kelly

Date: 06/10/2019

I the Admin Manager can confirm that this report is accurate to the paperwork received and this survey has been quality checked by myself.

Checked by: Emma Humphreys

Date: 07.10.2019

Report Compiled By

Armour Analytical Services Ltd, Admirals Yard, Station Road, Bristol, BS34 6LR

Document Name	Author	Issued by	Revision Number	Issue Date	Page No
2019	David Kelly	Armour AS	0	07/10/2019	19